BRUHAT BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

Draft Tender Schedule(DTS)

Name of Work: - Maintenance of Public Toilet In Ward No.13 Mallasandra Shetthalli Sub Division.

Sl No	Description of Work	Unit	Quantity as per Estimate	Rate to be Quotated	
				In Figures	In Words
1	KSRB 4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS (P.No. 12/I.No. 4.2 of PWD 2018-19)	Cum	31.73	5698.60	
2	Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications (Page No116, Item No.15.18, PWD SR 2018-19)	Sqm	146.42	316.25	
3	Providing 18mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering: providing and removing scaffolding, including cost of materials labour curing complete as per specifications(P.No. 112, I.No. 15.15 of PWD SR 2018-19)	Sqm	527.04	301.80	
4	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling incluidng rounding off corners wherever required smooth rendering providing and removing scaffolding including cost of materials, labour curing complete as per specification . (Page No. 116, Item No. 15.21 of PWD SR 2018-19)	Sqm	152.86	256.28	

Number of Corrections:

ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: Nil

ರದ್ದುಗೊಳಿಸಿರುವ ಪಟಂಗಳ ಸಂಖ್ಯೆ: Nil

Executive Engineer
Dasarahalli Division
BBMP - Bangalore

DTS APPROVED

ಕಂಡಿಕೆ(14) ರಲ್ಲಿ ವಿವರಿಸಿರುವ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು ದಾಸರಹಳ್ಳಿ ರವರು
ದೃಢೀಕರಿಸಿಕೊಳ್ಳುವ ಷರತ್ತಿಗೆ ಒಳಪಟ್ಟು ಟೆಂಡರ್
ಅನುಮೋದಿಸಿದೆ.
ಕರಡು ಟೆಂಡರ್ ಪೆಡ್ಯೂಲ್‌ನ್ನು [illegible] ಮಾಡಿದಂತೆ
ತಿದ್ದುಪಡಿ ಇಲ್ಲದೆ ಅನುಮೋದಿಸಿರುತ್ತೆ.

N.H

ತಿದ್ದುಪಡಿಗಳ: .....

ರದ್ದುಪಡಿಸಿರುವ: .....

[illegible]